

BRUHAT BENGALURU MAHANAGARA PALIKE (BBMP)

NAME OF THE WORK: Modified of Renovation and additional construction of RR nagar constituency MLA office, BBMP RR Nagar Division Executive engineer and Yeshwanthapura Sub Division Assistant Executive engineer office behind Chowdeshwari Bus stop, J.P Park and construction of compound wall in front of J .P Park in Ward no.17

PROVISION ABSTRACT						
Sl. No.	PARTICULARS	Area In Sq M		Statuas of Work	Amount In Rs	
		Previous Provision	Revised		Previous Provision	As Per Revised Estimate
1	M L A Office building	165.00	10.00	100%	9689431.00	2575330.62
2	Ampi Theater And Immersion tank			Cancelled	12173494.50	0.00
3	J P Park Front Compound wall (Sq M)	1039.50	2103.54	100%	7404037.00	23437448.29
	Length (Meter)	498.00	889.20	100%		
4	Parking lot	-	2037.20	Yet to Approval	-	6923971.87
5	Ramp	-	138.32	Yet to Approval	-	707896.00
Total Cost Revised					29267127.50	3,36,44,811.78

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF THE WORK: Modified of Renovation and additional construction of RR nagar constituency MLA office, BBMP RR Nagar Division Executive engineer and Yeshwanthapura Sub Division Assistant Executive engineer office behind Chowdeshwari Bus stop, J.P Park and construction of compound wall in front of J .P Park in Ward no.17

Sl	Descriptions	Unit	No	L	B	D	Qty.	Rate	Amount
1	Dismantling burnt brick masonry in clay mortar/lime mortar/cement mortar and stacking the bricks within a radius of 50m and removing the debris to a distance upto 200m.								
	Existing Wall in Ground Floor		1	6.20	0.23	2.85	4.06		
			1	6.20	0.23	2.85	4.06		
	Existing Toilet		1	4.00	0.23	2.85	2.62		
			1	4.00	0.23	2.85	2.62		
	Cum						Total Qty	13.37	
							Schedule B Qty	15.00	
							Total Qty	13.37	194.00
									2,594.21
	Dismantling the tile work in floor and roof laid in cement or surki mortar including stacking the materials with in 50 m lead of tiles thickness 10mm to 25mm.								
2	Room 1		1	6.20	7.50		46.50		
	Sqm						Total Qty	46.50	
							Schedule B Qty	431.00	
							Upto 125%	46.50	38.00
									1,767.00
3	Earth work for lowering & levelling the ground other than foundation works by Mechanical means upto 3.0 mt depth including providing shoring stutting and bracing , removal of stumps and other and other deleterious matter, dressing of sides and bottom, filling back the excavated earth to the extent required and utilising /transporting the remaining earth upto 1.00km lead. including cost of labour, materials and HOM of machineries etc., complete.								
	Toilet Wall		2	1.50	0.60	0.75	1.35		
			2	1.00	0.60	0.75	0.90		
	Jp Park Parking Place		1	76.00	28.50	0.58	1256.28		
	Cum						Total Qty	1258.53	
							Schedule B Qty	168.00	
							Upto 125%	210.00	84.00
							Above 125 %	1048.53	74.35
									17,640.00
									77,954.08
4	KSRB -2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.								
	For Park Compound Wall		1	190.10	1.30	1.20	296.56		
	Grond Side		1	397.50	1.30	1.20	620.10		
	Jp Park Footh Path		1	148.10	1.30	1.20	231.04		
	Jp Park Parking Place		1	23.50	0.90	1.00	21.15		
	Compound Wall		2	13.00	5.32	0.65	89.91		
	Ramp								
	Cum						Total Qty	1258.75	
							Schedule B Qty	1012.19	
							Total Qty	1258.75	235.00
	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.								
	Toilet Wall		2	1.50	0.60	0.15	0.27		
			2	1.00	0.60	0.15	0.18		
	For Park Compound Wall								
	Grond Side		1	190.10	1.30	0.15	37.07		
	Jp Park Footh Path		1	397.50	1.30	0.15	77.51		

Sl	Descriptions	Unit	No	L	B	H	Qty	Rate	Amount
6	Jp Park Parking Place Compound Wall Ramp		1	148.10	1.30	0.15	28.88		
			1	23.50	0.90	0.15	3.17		
			2	13.00	5.32	0.15	20.75		
		Cum					Total Qty	167.83	
							Schedule B Qty	130.40	
7	Construction of embankment with approved material Gravel/Murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murum, watering charges & compaction by vibratory roller to 95% of proctors density		1	76.00	28.50	0.50	1083.00		
			-58	2.22		0.40	-51.50		
		Cum					Total Qty	1031.50	
							Schedule B Qty	248.00	
							Upto 125%	310.00	375.00
8	KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406		1	76.00	28.50	0.15	324.90		
			-58	2.22		0.15	-19.31		
		Cum					Total Qty	305.59	2301.07
									7,03,175.31
7	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix M15 with cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specification. Specification No. KRS 4.1, 4.2								
		Coping							
		For Park Compound Wall							
		Ground Side	1	190.10	0.60	0.125	14.26		
		Jp Park Footh Path	1	397.50	0.60	0.125	29.81		
7	Jp Park Parking Place Compound Wall		1	148.10	0.60	0.125	11.11		
			1	23.50	0.20	0.125	0.59		
		Cum					Total Qty	55.77	
							Schedule B Qty	28.20	
							Upto 125%	35.25	6757.00
7	Providing & laying IN POSITION REINFORCED CEMENT CONCRETE of design mix M25 with OPC cement @ 340 Kgs with down size graded granite metal coarse aggregates @ 0.70 Cum & fine aggregates @ 0.47 Cum with super plastisiser @ 3.0 Ltrs confirming to IS 9103-1999, re affirmed - 2008, Machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation, Plinth, & Ground floor Level for Roof Slab, Staircase, Lintels, Retaining Wall, Piers, Abutments, Pillers, Posts, Struts, Butteress, String or Lasing Corssess, Prapectts Copings, Bed Blocks, anchor blocks, plain windows cills, filliets, etc including cost of all materials, laobur HOM of machinery, curing complete as per specification. -First Floor								
8	Toilet Wall Plinth Beam		2	1.50	0.20	0.20	0.12		
			2	1.00	0.20	0.20	0.08		
		Jp Park Parking Place	1	76.00	28.50	0.15	324.90		
		Deduction Tree's	-58	2.22		0.15	-19.31		
		Ramp	2	13.00	5.32	0.50	69.16		
8							374.95		
							Total Qty	374.95	
							Schedule B Qty	48.00	
							Upto 125%	60.00	7787.00
							Above 125%	314.95	7083.60
8									

SI	Descriptions	Unit	No	L	B	D	Qty.	Rate	Amount
	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 - Ground Floor								
	Toilet Wall Plinth Beam		4	1.50		0.20	1.20		
			4	1.00		0.20	0.80		
			4	13.00		0.50	26.00		
9	Ramp						28.00		
		Sqm					Total Qty	28.00	
							Schedule B Qty	50.00	
							Total Qty	28.00	318.00
									8,904.00
	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 -Ground Floor								
	Toilet Wall Plinth Beam						0.05	Ton	
	Qty Vide From Calculation Sheet								
10	Jp Park Parking Place		1	76.00	28.50		2166.00	Sqm,	
	Consider 6.75 Kg/ Sqm		-58	2.22			-128.76		
	Deduction Tree's						13751.37	Kg's	
							13.75	Ton	
	Ramp		2	13.00	5.32		138.32	Sqm,	
	Consider 8.75 Kg/ Sqm						760.76	kg's	
		Ton					0.76	Ton	
							Total Qty	14.56	
							Schedule B Qty	61.74	
							Upto 125%	14.56	75261.00
									10,95,960.00
ERL 2	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS.								
	Jp Park Parking Place	Sqm	1	76.00	28.50		2166.00		
	Deduction Tree's		-58	2.22			-128.76		
							Total Qty	2037.24	1283.38
									26,14,560.00
11	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13								
	Toilet Wall	Cum	2	1.50	0.45	0.45	0.61		
			2	1.00	0.45	0.45	0.41		
	For Park Compound Wall								
	Grond Side		1	190.10	1.00	1.20	228.12		
	Jp Park Footh Path		1	397.50	1.00	1.20	477.00		
	Jp Park Parking Place		1	148.10	1.00	1.20	177.72		
	Compound Wall		1	23.50	0.60	0.45	6.35		
	For Park Compound Wall								
	Grond Side		1	190.10	0.60	1.80	205.31		
	Jp Park Footh Path		1	397.50	0.60	1.60	381.60		
	Jp Park Parking Place		1	148.10	0.60	1.60	142.18		
	Compound Wall		1	23.50	0.40	0.45	4.23		
							1623.51		
							Schedule B Qty	167.08	
							Upto 125%	208.85	2166.00
							Above 125%	1414.66	6682.61
									4,52,369.10
									94,53,637.60

Sl	Descriptions	Unit	No	L	B	D	Qty.	Rate	Amount
12	Construction of partition wall 11.2 cms thick with non modular table moulded burnt bricks of class designation 5.0 Newton per Sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm -Specification No. KBS 6.2 - Ground Floor								
	Toilet Wall		2	1.50		2.85	8.55		
			2	1.00		2.85	5.70		
			-2	0.75		2.10	-3.15		
	Deduction Door	Sqm				Total Qty	11.10		
						Schedule B Qty	32.00		
						Upto 125%	11.10	1159.00	12,864.00
13	Providing & constructing non load bearing walls with solid concrete blocks of size 400x100x200 having block density not less than 1800 Kg /m3 having a min average compressive strength not less than 4.0 N/ mm2 confirming to I.S. : 2185 (part 1) 2005 & constructed with C M 1: 4 C M 1: 4 as per IS 2572: 2005 including cost of materials, labour charges, scaffolding, curing complete as per specification.- Ground Floor								
	Toilet Wall		58	5.1		0.40	118.32		
	Surrounding Tree	Sqm				Total Qty	118.32		
						Schedule B Qty	107.20		
						Upto 125%	118.32	889.00	1,05,186.00
14	Providing 18mm thick cement plaster in single coat with cement mortar 1:3 to Brick masonry including rounding off corners wherever required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications Out Side walls- Ground Floor								
	Toilet Wall		4	1.50		2.85	17.10		
			4	1.00		2.85	11.40		
			-2	0.75		2.1	-3.15		
	Deduction Door	Sqm				Total Qty	25.35		
						Schedule B Qty	496.50		
						Upto 125%	25.35	303.00	7,681.00
15	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification.								
	Room		2	6.20		7.5	93.00		
		Sqm				Total Qty	93.00		
						Schedule B Qty	251.25		
						Total Qty	93.00	1381.00	1,28,433.00
16	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size 30x30cms - Ground Floor								
	Toilet		2	1.50	1.00		3.00		
		Sqm				Total Qty	3.00		
						Schedule B Qty	82.00		
						Total Qty	3.00	1461.00	4,383.00
17	KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.- Colour glazed tiles 15◆15cms 6mm thick with border of size 15◆15x6cms- Ground Floor								
	Toilet	Sqm	2	5.00		1.50	15.00		
	Deduction Door		-2	0.75		1.50	-2.25		
						Total Qty	12.75		
						Schedule B Qty	848.10		
						Total Qty	12.75	1390.00	17,722.50

Sl	Descriptions	Unit	No	L	B	D	Qty.	Rate	Amount
	Providing & applying Two coats of wall putty to inside plasterd walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of materials , cost of labour and scaffolding etc complete as per specifications								
	Toilet Wall	Sqm	4	1.50			2.85	17.10	
	Toilets		4	1.00			2.85	11.40	
			-2	0.75			2.10	-3.15	
18	Deduction Of Door							-12.75	
	Deduction Wall Tiles								
							Total Qty	12.60	
							Schedule B Qty	1305.50	
							Total Qty	12.60	70.00
									882.00
	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - do- with primer-INSIDE-Ground floor								
	Toilet Wall	Sqm	4	1.50			2.85	17.10	
	Toilets		4	1.00			2.85	11.40	
19			-2	0.75			2.10	-3.15	
	Deduction Of Door							-12.75	
	Deduction Wall Tiles								
							Total Qty	12.60	
							Schedule B Qty	848.10	
							Total Qty	12.60	112.00
									1,411.20
	Providing and fixing M.S. Grill over existing compound wall as per using 16mm x 16mm M.S. Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification								
20	For Park Compound Wall								
	Grond Side		1	204.20			2.40	490.08	
	Jp Park Footh Path		1	417.40			2.40	1001.77	
	Jp Park Parking Place		1	244.10			2.40	585.84	
	Compound Wall		1	23.50			1.10	25.85	
		Sqm					Total Qty	2103.54	
							Schedule B Qty	1039.50	
							Upto 125%	1299.38	6483.00
							Above 125%	804.16	6543.67
									84,23,848.13
									52,62,174.29
	Providing TEAK WOOD frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications								
21	Room Doors	Cum	2	6.00	0.10	0.23	0.28		
							Total Qty	0.28	
							Schedule B Qty	0.35	
							Total Qty	0.28	230865.00
									63,718.74
	KSRB 9.5-1 : Providing and fixing in position fully panelled Teak wood shutters for doors, with styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawingand panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34								
22	Room Doors	Sqm	2	0.90		2.00	3.60		
							Total qty	3.60	
							Schedule B Qty	5.80	
							Total Qty	3.60	10311.00
									37,119.60

	Descriptions	Unit	No	L	B	D	Qty.	Rate	Amount
13	Providing and fixing of factory made 30 mm P.V.C door frame of size 50x47 mm with a wall thickness of 5 mm made out of extruded 5 mm rigid PVC foamsheet metered cut at corners & jointed 2 nos 150 mm long brackets of 15 x 15 mm MS Square tube, the entire door frame to be reinforced with 19 x 19 mm square tube of 19 gauge. the door frame to be fixed to the wall using MS screws of 65 /80 mm size complete as per manufacturers specification & directions of Engineer in charge.								
	Toilet Doors		2	5.70			11.40		
		Sqm					Total Qty	11.40	
							Schedule B Qty	96.90	
							Total Qty	11.40	484.00
									5,517.60
24	Providing & fixing 30mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19 x 19mm for styles and 15 x 15mm for top and bottom rails, covered with heat moulded PVC channel of 5mm thick sheet & 30 x 50mm wide to form styles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the styles & rails with 5 x 30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75 mm Aluminium hinges.- Ground Floor								
	Toilet Doors		2	0.75		2.10	3.15		
		Sqm					Total Qty	3.15	
							Schedule B Qty	23.70	
							Total Qty	3.15	3974.00
									12,518.10
25	Providing & fixing of glazed 2 Track-2 Panel Sliding Windows made out of multi Chamered uPVC sections with TPV(Thermo Plastic Vinyl) gaskets having Isolated drainage and reinforced with Galvanized iron profiles through out the window. The outer frame having a overall size of 60x45 mm with reinforcement of 1 mm thickness and sash with overall size of 39x58 mm with reinforcement of 1.5mm thickness. Glazing bead for fixing of glass shall be of size 20x18mm and coextruded with gasket. Windows shall be provided with 5mm plain float glass, standard hardware & single point locking system of flush lock, Wall thickness of frame & sash shall be 2-2.2 mm.								
	Windows								
			5	0.90		1.20	5.40		
			1	1.50		1.50	2.25		
		Sqm					Total Qty	7.65	
							Schedule B Qty	15.10	
							Total Qty	7.65	7947.00
									60,794.55
26	KSRB 7.14 : Providing, fabricating, assembling and fixing in position aluminium partitions using sections in combination of plain, single grove and double grove as per requirements for the frames of overall size 101.6mm x 44.45mm, 3.18mm.thick having section weight, plain sections 2.40kg/m single grove section 2.541kg/m. and double grove section 2.683 kg/m and bottom bottom member 114.3 mm x 44.45 mm 3.18 mm thick and 2.6 46 kg/m; aluminium louvres of size 77.6mmx27.6mm 1.7mm. thick section weight 0.483kg/m; bottom portions provided with 12mm. thick pre laminated sheet both side of approved colour lamination exterior grade; aluminium sections of mat finish or glossy finish using section, spacing of vertical member shall not exceed 0.6 m. c to c; sections are cut to the required lengths, joints mitred and corners grinded subdividing frames tennoned and riveted to the frames, the assembled frame should be stiffened with corner angles stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns or masonry on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistling and making good with cement mortar to match the surface, providing and fixing bottom panel filled with the materials to a height of 0.9m. from floor level; and 5.5mm. thick plain glass for middle portion viz., 0.9m. to 2.13 m. and top panel with lower sections, the glass and panels fitted with glazing clips of 19mmx17.3mm. with thickness of 0.9mm. weight 0.124kg/m; aluminium sections pre-treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non-adherence of mortars or any other sticky materials; vertical members embedded in the flooring by making suitable size holes and fixing with cement mortar, with necessary opening for fixing of doors of standard size (excluding cost of door opening) All the frame should be thoroughly cleaned free from rust, scale or dirt including cost of materials, fixtures, labour and HOM of machinery complete as per specifications.								
	Room								
		Cabin	1	7.50		3.00	22.50		

Descriptions	Unit	No	L	B	D	Qty.	Rate	Amount
Deduction Cabin Door	Sqm	1	5.00		3.00	15.00		
		2	0.90		2.10	3.78		
					Total Qty	33.72		
					Schedule B Qty	32.20		
					Total Qty	33.72	5875.00	1,98,105.00
27 KSRB 7.17 : Providing, fabricating, assembling and fixing in position aluminium doors using following aluminium mat finish or glossy finish, outer frame plain section 101.6x44.45mm thickness 3.18mm, section weight 2.404 kg/m, door shutters vertical section 44.62x44.45mm thickness 3.18mm, section weight 1.505kg/m, top section 47.62x44.45mm thickness 3.00mm, section weight 1.426kg/m bottom section 114.3x44.45 thickness 3.18mm, section weight 2.646kg/m, door central section 49.91x44.45mm thickness 3.00mm, section weight 1.495 kg/m glazing clips 19x17.3x11mm thickness 0.9mm section weight 0.124kg/m; aluminium sections cut to length joint metred corners grinded, the shutters pivoted opening arrangement with heavy duty aluminium alloy automatic door closures floor mounted, providing and fixing standard approved accessories, such as aluminium handle for full width or length, tower bolts, lock pivots P.V.C or rubber gasket with 5.5m. thick plain glass for top and bottom panels aluminium sections treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for								
Room	Cabin Doors	2	0.90					
	Sqm							
					Total Qty	3.78		
					Schedule B Qty	7.60		
					Total Qty	11.38	7836.00	29,620.08
28 Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11								
Wc		2				2.00		
	No's							
					Total Qty	2.00		
					Schedule B Qty	3.00		
					Total Qty	2.00	6370.00	12,740.00
29 KSRB 11-11.1 : Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11								
Wc		2				2.00		
	No's							
					Total Qty	2.00		
					Schedule B Qty	14.00		
					Total Qty	2.00	4826.00	9,652.00
Sub Total							3,36,44,649.42	
Miscellaneous & Rounding off							1,379.22	1376.8
Grand Total							3,36,46,026.00	

CERTIFICATE

- 1) Certified that the Estimate prepared with necessary provisions as Per site conditions.
- 2) Certified that the estimate is prepared on the basis of PW,P & IWTB Bangalore Circle, for the year 2018-19 and Data Approved Rate
- 3) Certified that the above area comes under BBMP limits

[Signature]
Project Division, RR Nagar
B.B.M.P

[Signature]
Assistant Executive Engineer
Project Division, RR Nagar
B.B.M.P

Bruhat Bangalore Mahanagar Palike
Rajarajeshwari Nagar Zone

[Signature]
Executive Engineer
Project Division, RR Nagar
B.B.M.P

Bruhat Bangalore Mahanagar Palike
Rajarajeshwari Nagar Zone